



Trenching - Cable trenches shall have vertical walls and be excavated to a depth that permits cables to be laid at 2'-0" below finish grade with a 3" sand cover above, below, and on each side.

Sand shall pass a 1/4" sieve and be poured and left uncompacted.

Cables shall be unreeled and placed in trench in sand bed.

Backfilling - Material for backfilling shall be clean earth from the site free of debris and stones. Compact backfill to 95% modified proctor.

APPROVED
EVANS, MECHWART, HAMBLETON & TILTON, INC.

By

Charles W. Bond Jr.
CITY ADMINISTRATOR

STREET LIGHTING TRENCH DETAIL

CITY OF
GROVE CITY, OHIO

STANDARD
CONSTRUCTION DRAWING

DATE
8-21-87

DWG. NO
C-GC-49